

5th corrigendum to the Tender Schedule No 371654 dated 30.11.2022

Considering the suggestions received at pre bid meeting conducted on 15.12.2022, the rate and quantity against the post tensioning item (sl No 130 of BOQ) are corrected as below

Sl.No.	Quantity	Description of Work	Short specification	Item Description	APDSS Number	Rate	Unit (in words)	Amount
136	18.753	Design and execution of post tensioning work, including supplying, laying of HT tendon strands, decoiling, the strands, cutting to the required lengths, laying of HT strands in sheathing (GI corrugated ducts 0.3mm thick) jointing with couplers and inserting the strands, profiling, fixing live end anchorages, making dead end anchorages, including flowering the strands, fixing tendon support bars, supervising the fixing of antibursting reinforcement, stressing the cables using hydraulic jack, end trimming, grouting the cables, with cement slurry, mixed with admixtures with required tools, plants, and machineries, and consumables etc., including all leads, lifts, coordination, with the posttensioning agency, preparation of drawings, obtaining approval from the Engineer-in-Charge with supply of approved grade tendons but excluding the cost of concrete, reinforcement steel, shuttering, anchors, sheathing duct etc.,including sales and other taxes on all materials etc. ,and overheads & contractors profit complete for finished item of work For all Floors	Design and execution of post tensioning work	Design and execution of post tensioning work	As directed by Engineer in charge	2,30,626.00	ONE MT	4324834